

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of the Work: Improvements to roads and drains of Balaji Layout amruthahalli in ward 07, Byatarayanapura

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	437.75	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.. Pg No.141,Item No.19.1)	Cum	86.92	
2	201.38	KSRRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification . (Pg.No.12, It.4.3)	Cum	5159.02	
3	134.25	Cement concrete pavement. Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 with 25mm and down size graded granite metal coarse aggregates and fine aggregates with superplasticiser @ 3lts confirming to IS9103-1999 REAFFIRMED-2008. Mixed in a concrete mixer of not less than 0.6 cum capacity and approximate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing) and spreading the concrete with shovels, rammers compacted using needle, screed and plate vibrator and finished in a continuous operation including, provision of contraction, expansion, construction operation including longitudinal joints, including groove cutting charges joint filler, separation membrane, sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specification.M20 (AT 300 Kg per cum coarse aggregates @ 0.69cum and fine aggregate @0.43cum) (Pg No.177, It No.22.6.1)	Cum	6217.96	
4	437.75	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 (Page 118, item No. 17.1)	Cum	106	

[Signature]
Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92
83/07

[Signature]
23/07

Note:

- Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed
- Unit rates and prices shall be quoted by the Tender in Indian rupees.
- Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

[Signature]
ಮುಖ್ಯ ಅಧೀಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.